



Volume = 2375.04 Gallons  
 Volume = 43.08 Gallons per inch  
 Weight = 9688# per Half (19,376# total)

**Notes:**

1. Optional tank risers should be ordered to grade.
2. Minimum 4500 psi at 28 days concrete.
3. Reinforcing bars shall conform to ASTM A-615 Grade 60 Steel.
4. All reinforcing bars shall be cut and formed to the dimensional tolerances specified in ACI-315 or ACI-318 except where noted on drawings.
5. All bars shall be bent cold. Bars with kinks and bends not indicated shall not be used. Heating and rebending of bars is not permitted.
6. Reinforcing steel shall be #4 rebar at 12" o.c. both ways tied to 6x6 8/8 Welded Wire Mesh.
7. Earth cover: 0' minimum up to 5'-0" maximum. Size pad according to amount of earth cover.

Drawing Name:  
 2000-2ST 2015  
 Date:  
 1/26/15  
 Revised:

**2000 Gallon**  
**Two Compartment**  
**Septic Tank**

**MIDWEST TILE & CONCRETE PRODUCTS, INC.**  
 4309 Webster Road  
 Woodburn, IN 46797  
 Phone: 260-749-5173  
 Fax: 260-493-2477  
 6209 Ardmore Ave  
 Fort Wayne, IN 46809  
 Phone: 260-478-9098  
 Fax: 260-478-6738